# SPECIFICATIONS REPORT

# Alya Mijas

# Malaga





#### FOUNDATION AND STRUCTURE

Foundations and reinfarced concrete structure according to current regulations.



Façade cladding based on brickwork, covered with plaster and exterior paint. Interior thermal insulation, air chamber, lined with interior plasterboard partitioning, fixed with metal.

Protection of terraces with factory breastplates or metal railings and safety glass, depending on the exterior design.

# **ROOFING**

Flat inverted non-passable roof with gravel finish. Walkable cover finished with exterior non-slip stoneware.

#### **EXTERIOR CARPENTRY**

Metal pre-frame carpentry in façade gaps, with thermal bridge breaking, farming a join between carpentry and glass far improved thermal and amustie insulation, according to regulations.

Bedroom blinds, with aluminum or PVC slats and injected thermal insulation.

Double glazing with air chamber farming high thermal and amustie performance.

# INTERIOR DIVISIONS

Interior partition walls of homes in laminated plaster, with load-bearing metallic structure and interior thermal-acoustic insulation.

Dwellings are separated by ceramic partition walls and laminated plaster cladding with thermal-acoustic insulation on both sides.

# INTERIOR CARPENTRY

Lacquered armoured door to enter the homes with grooves, security fittings, exterior handle and optical peephole.

Flat-leaf interior doors with horizontal grooves, a white lacquered finish, hanging fixtures and handle.

Modular, hinged or sliding cabinets depending on the type, to match the doors. Cabinet interiors finished in melamine, with luggage shelf and hanging rail.

#### **PAINTS**



#### PAVEMENTS AND CLADDINGS

60.5\*60.5 ceramic stoneware flooring throughout the home with white lacquered MDF skirting board.

High quality ceramic tiling in bathrooms.

Smooth false ceiling throughout the home. False ceiling accessible from the bathroom far installation of air conditioning machinery. Interna! machine registration. Ceramic flooring and surfaces.

Mixed coating of plastic paint and high quality ceramic tiling in the kitchen work area, according to design.

#### AIR CONDITIONING AND HOT WATER

Individualized Aerothermal System for air conditioning and DHW.

Installation for air conditioning through ducts with grilles in the living room and bedrooms, with indoor unit.

This technical specification is provisional and subject to changes originated by License requirements or by criteria of the Facultative Management, without detrirnent to the quality. Technical specification 06/06/2023 version V-0.1



# SPECIFICATIONS REPORT





# SANITARY APPLIANCES AND TAPS

Vitrified porcelain sanitary ware in white.

Extra-flat shower in main bathroom. Thermostatic faucet in shower of main bathroom and mixer taps in sink. Sink cabinet in main bathroom.

Mirror in bathrooms



#### **ELECTRICITY AND TELECOMMUNICATIONS**

Electrical installation in accordance with Low Tension Electrotechnical Regulations.

Telecommunications installation in the home (basic telephony and cable telecommunications) with sockets in living room and bedrooms.

Water and electricity connection on the terrace.



#### FURNITURE AND KITCHEN EQUIPMENT

Furnished kitchen with compact worktop and equipped with electrical appliances.

Distribution according to property type.

Appliances: electric oven, ceramic hob, built-in hood, refrigerator and dishwasher.

Stainless steel sink and mixer tap.



#### COMMUNAL AREAS, URBANIZATION AND VARIOUS

Fully enclosed and fenced residential complex.

Low consumption lighting in entrances, interior roads and gardens.

Outdoor saline chlorination community pool with night lighting system.

Garden areas with lawn areas, tree and/or shrub species.

Gymnasium, co-working area.



#### COMMUNAL AREAS, URBANIZATION AND VARIOUS - continued

Electric vehicle charging facility.

Common areas in stoneware tile, cobblestone or stamped concrete pavement according to zone.



#### **ENERGY RATING**

This energy efficiency rating is merely informative, provisional and subject to modifications in the project phase.



This technical specification is provisional and subject to changes originated by License requirements or by criteria of the Facultative Management, without detrirnent to the quality. Technical specification 06/06/2023 version V-0.1

